

Village of Innisfree
Special Council Meeting
Seniors Drop-in Centre, Innisfree AB
June 11, 2019 @ 7:00 p.m.



AGENDA ADDITIONS

New Business:

- h. [West Lift Station Upgrades – Quote dated June 10, 2019](#)
- i. HWY 870 (between 48th & 50th Avenue) Temporary Road Repairs

Town of Innisfree

West Lift Station

On May, 29/2019 we visited the West Lift Station along with an electrician from Vector. The following was discovered upon arrival.

One pump had tripped the breaker and the other was over loaded. Ben from Vector reset both pumps and the pumps seemed to function correctly. One relay in the panel was seized and not functioning. This relay is in need of replacement. The overall electrical components of the system are functioning but are in poor condition. It would be recommended that this be upgraded in the near future.

When the pumps were running the effluent was spraying out the side of one of the check valves. The other check valve had some leakage as well. This explains why the pumps had tripped as they were pumping but the effluent was not going anywhere. It would just cycle the effluent inside the lift station.

The piping, valves, and guide bars are in poor condition and require replacement for the lift station to function correctly.

If there are any questions or concerns regarding the above findings and recommendations, please feel free to contact me on my cell (780-719-9257) or via e-mail at aaronqqr@telus.net.

Best Regards,

Aaron Mol

QQR Mechanical Contracting Ltd.

Q.Q.R. MECHANICAL CONTRACTING LTD.

P.O. BOX 3176
Sherwood Park, AB T8H 2T2

Tel: (780) 467-8734
Fax: (780) 467-8720

QUOTATION

To: Village of Innisfree

Q2020-INF

ATTENTION: Brooke Yaremchuk

DATE: 6/10/2019

We thank you for the opportunity of submitting the following prices.

Re: West Lift Station

We are pleased to provide our firm price to supply/install the mechanical components of the project noted above as per the breakdown and exceptions below.

Schedule


1 Demolition and replacement of piping, valves, and guide bars with SS pipe, HDL check valves, and plug valves only.	\$13,309.00
2 Replacment of faulty electrical relay only.	\$1,595.00
3 Replacement of double door hatch with aluminum hatch only.	\$5,645.00

Total For This Quotation \$20,549.00
GST Not Included

Not Included In This Quotation:

Temporary pumping/vac truck during work. Discharge bases and pumps. Floats and other electrical components.

*Quotation Open For Acceptance For 30 Days From Date of Issue


Aaron Mol